ZITHA TECH SPECIALTY CABLES (Pty) Ltd

How to install the network cable terminal box on each floor



Overview

This video was associated with the source search result. Verify technical details against current product documentation and project requirements.

Key Takeaways

To install a network cable terminal box on each floor, plan the location, run cables through walls or conduits, secure the box, and ensure fire safety and code compliance.Step 1: Plan the Terminal Box Location

Choose a central, accessible location on each floor, such as a utility closet or near existing network nodes. Ensure the area has enough space for the terminal box, switches, and cable management. Consider future expansion and proximity to devices that will connect to the network .

Step 2: Select the Cable and Conduit

Use Cat6a or higher Ethernet cables for high-speed, future-proof connections. For protection and organization, run cables through conduits such as EMT (metal), PVC, or flexible ENT tubes. Conduits shield cables from physical damage, moisture, and electromagnetic interference, and allow easy upgrades .

Step 3: Prepare the Path Between Floors
• Inspect walls and floors for obstructions like electrical wiring, plumbing, or HVAC ducts .

© 2026 ZITHA TECH SPECIALTY CABLES (Pty) Ltd - All rights reserved

• Use a stud finder and non-contact voltage tester to avoid hazards .

• Drill holes through floor plates or wall studs using an auger bit (1/2–3/4 inch) at a slight angle to guide the cable safely .

• Install firestopping foam around penetrations to prevent fire spread .

Step 4: Run the Cable

• Use fish tape or glow rods to guide the cable through walls or conduits .

• Attach the cable securely to the fishing tool and pull slowly, maintaining a gentle curve to avoid damaging the twisted pairs .

• Ensure cables cross power lines at 90-degree angles to minimize interference .

Step 5: Mount the Terminal Box

• Secure the terminal box to the wall or inside a closet using screws or brackets.

• Install patch panels or keystone jacks inside the box for organized connections.

• Label each port clearly for easy identification and maintenance .

Step 6: Connect and Test

• Terminate the cables at the patch panel or keystone jacks.

• Connect switches or routers inside the terminal box.

• Test each connection with a network cable tester to ensure proper signal integrity and performance .

Step 7: Maintain and Future-Proof

• Leave extra cable length in the box for future upgrades.

• Keep a pull string in the conduit for adding new cables without wall damage .

• Regularly inspect the installation for wear, moisture, or interference issues. By following these steps, you can create a safe, organized, and scalable network infrastructure across multiple floors, ensuring reliable connectivity and easy maintenance.

© 2026 ZITHA TECH SPECIALTY CABLES (Pty) Ltd - All rights reserved

Article Content

Network Cabling Installation Guide: Step-by-Step Process (2025)

7 Steps For Network Cabling InstallationHere''s A Quick LookWhat Not to Do in Network InstallationBest Practices in Network InstallationHazards of Network InstallationConclusionNetwork wiring installation has a few basic steps: 1. Create a central hub where the router and networking switch will be located 2. Create an outlet near the hub, and another where networked devices will be 3. Run the cable through the walls 4. Connect the cable at each end 5. Fit outlets with faceplates 6. Test connection 7. Configure and connect...See more on thenetworkinstallers The Black Urban Times

How to Run Ethernet Cable Between Floors: Step-by-Step Guide

Learn how to run Ethernet cable between floors by understanding the process of safely routing cables through walls and ceilings for

Related Video Reference

This video was associated with the source search result. Verify technical details against current product documentation and project requirements.

Contact Us

Continue your research online:

Website: https://zithatech.co.za
Technical inquiry: https://zithatech.co.za/contact.html

This document is for preliminary research. Verify specifications against current standards, product documentation and project requirements.

© 2026 ZITHA TECH SPECIALTY CABLES (Pty) Ltd - All rights reserved